





# Total Project Planning – Case Study 3: *BNCS* Building

Building Nonstructural Components & Systems Project



Tara C. Hutchinson, Professor
UC San Diego
December 15, 2015



#### **Outline**

#### Motivation

Terminology, Justification

#### Project Overview

Vision, Scope, Resources (human & \$\$),
 Timeline

#### > Specifics

 Design, Construction, Instrumentation, Test Planning & Sequencing, Execution Guidance

#### > A Few Important Findings

(there are many)

#### Project Accolades

#### What is an NCS?

- Nonstructural Components & Systems = NCS = common short name adopted in a number of building design codes. Visual elements around us in finished structures...
- Supported by primary structural system not contributing to primary structural system load bearing needs
- Lightweight & low stiffness, compared with supporting structure
  - Low damping (lack protection from sharp resonant motions)
- Designed for functionality often not considering earthquake loads
- > Often termed "secondary" systems
- Broad classification: 1) MEP
   (mechanical/electrical/plumbing), 2) Architectural & 3)

Contents

## Consequences of NCS damage

- Major problem during rescue operations
- Loss of functionality, facility downtime
- Excessive economic losses
- > Threat to life



Calexico Schools 2010 Baja California EQ


- Hospitals & other critical facilities: post-earthquake operability of NCSs are essential (life saving equipment)
- Numerous NCSs play a critical role in minimizing postearthquake fire impacts – <u>fire protection NCSs</u>

## Project Motivation: 2011 Tohoku Earthquake, Japan

Sendai Mediatheque (library, constructed 2000)

Plaster board ceiling





Before the earthquake

After the earthquake

Courtesy of Shojiro Motoyui

Vision, Scope, Resources, Timeline


## **PROJECT OVERVIEW**

## **Project Vision**

- To make breakthrough advances in the understanding of total building systems performance (structural and nonstructural systems) under moderate and extreme seismic conditions through full-scale testing.
- Obtain data, which are sorely needed to characterize the earthquake performance of structural and nonstructural building systems, including nonstructural systems with protective measures.
- Use this data to validate nonlinear simulation tools, which in turn can be used for higher-performance code design and performance-based seismic design of nonstructural and building systems.
  - Infuse findings into seismic design guidelines and codes
    - Validate current code assumptions
    - Advance current code guidelines

#### **Project Overview**

Three-phased full-scale test program conducted on a 5-story building-NCS system ("total building system")





#### **Summary of Major NCSs:**

Egress systems:

- OperableElevator
- Stairs
- Facades:
  - Concrete cladding
  - Balloon framing
- Hospital equipment
- Roof mounted

equipment

- Sprinkler and riser systems
- Ceilings
- Interior partition walls



**HVAC** 



## **Testing Scope & Project Resources**

#### > Three Test Phases

- 1. Base isolated building-nonstructural system
- 2. Fixed base building-nonstructural system
- 3. Controlled live fire tests
- > ~5M US\$, multi-organizational 4 year project (2010-2014)
  - NSF-NEES core research project \$1.2M
  - Englekirk Advisory Board \$1.5M (est)
  - Charles Pankow Foundation \$250k
  - California Seismic Safety Commission (hospitals) - \$360k
  - Industry consortium remainder \$
     resources, materials, equipment, technical
     expertise, etc.



## Large, Multi-disciplinary Team

- Core Project Team (>20 faculty, students, engineers)
  - UCSD, SDSU, Worcester Polytechnic & Howard University
- Advisory Boards
  - Industry steering committee (ISC) (>40 companies)
    - ✓ Manufacturers, Sponsors, Technical Advisors
  - Engineering & regulatory advisory committee (ERAC) (10)
    - ✓ Technical oversight (code-perspective)
  - Academic/international liaison group (AILG) (10)
    - ✓ Technical oversight (academic perspective)
  - Englekirk Advisory Board (EAB)
    - ✓ Building (skeleton) design & funding
- Federal & state partners, foundations
  - NSF-NEESR, California Seismic Safety Commission, California Hospital Authority, Charles Pankow Foundation, FEMA

More than 300 individuals interacting within this project!

## **Core Team**

Name	Affiliation	Name	Affiliation
Tara Hutchinson (PI)	UC San Diego	Consuelo Aranda	San Diego State University
José Restrepo (Co-PI)  Joel Co Ken Wa  Claudia Robert  Brian M  Matt Ho  Robert Englekin	UC San Diego  Sabol Consulting S.E., inc.		ate University  D D D D D D D D D D D D D D D D D D
Mahmoud Faghihi	Englekirk & Sabol Consulting Structural Engineers, inc.		

#### **Partners**







Funded by the National Science Foundation under Grant no.: CMMI-0936505

Academic: University of California, San Diego (UCSD), Worcester Polytechnic Institute (WPI), San Diego State University (SDSU), and Howard University (HU)

Broad stakeholder participation (industry and government)





## **Industry Partners**

























Sto







by Schneider Electric











































**STANLE** 


**Healthcare Solutions** 





## e.g. Hilti Team (32 individuals >10%!)





## **Design & Construction**

## **SPECIFICS**

#### **Shake Table Specimen Design Questions**

#### What type of structural skeleton is needed?

- Structural skeleton role: provide a vehicle for delivering demands to NCSs (accelerations & deformations)
- Many iterative discussions, options...
  - ♦ Flexible steel frame-braced structure
  - ♦ Stiff steel braced structure
  - ♦ Podium-style (lower concrete wall & upper flexible frame)
  - ✓ Reinforced concrete frame-braced
- Decisive aspects: cost (design team), balance between benefits of flexible frame (expect large lower floor drifts) & nominally large accelerations (upper floors); shake table platen size

#### What types of nonstructural components are essential?


- Secure the key "bad actors" (or those lacking data!) early on prior to NEESR proposal submission e.g. (egress, façade, passive & active fire systems)
- "If we build it they will come"

## **Structural System**


- Design (criteria community decision):
  - Downtown LA (site class D; 7 MCE motions, 3 service motions; 2-2.5% design interstory drift ratio, peak ~0.7-0.8g floor acceleration)
- Poured-in-place concrete
- 2 bay x 1 bay; pair of SMRF (shaking direction)
- 4.2m story heights; 5 floors; 21.3m +
   1.5m foundation + 4m tower = 26.8m (tallest on UCSD table)
- Elevator shaft and stairway openings at floor diaphragms
- ▶ 10.4m x 6.1m c/c footprint
- ~ 1 sec longitudinal (fixed base)
- ~2.5 sec longitudinal (base isolated)




- Bare structure: ~4900kN
- Building+NCSs: ~6300kN
- $\triangleright$  (Foundation = 1870kN)




## **Roof Mounted Equipment**





**Exterior Facades** 

**Architectural Precast Concrete Cladding** 




Balloon-framed metal stud+EIFS

**NW View** 



## **Construction Management**

- During construction, such a complex project needed careful planning. For this effort, SDSU led a comprehensive construction management effort
  - Coordinating all superstructure construction phasing
  - Coordinating all nonstructural installation phasing
  - Documenting on-site deliveries
  - Dealing with construction delays (reorganizing subs)
  - We held multiple planning meetings (2009, 2010, 2011) with all industry partners & researchers





#### Construction (Superstructure)



**ROOF SLAB:** 

September 21st,2011

FIFTH FLOOR SLAB:

September 6th, 2011

**FOURTH FLOOR SLAB:** 

August 19th, 2011

**THIRD FLOOR SLAB:** 

August 3rd,2011

**SECOND FLOOR SLAB:** 

July 15th, 2011

**FOUNDATION:** 

June 27th,2011






## **Construction (Nonstructural)**

_					
	2011				
	January	February	March	April	
	Mo Tu We Th Fr Sa Su				
	31 1 2	1 2 3 4 5 6	1 2 3 4 5 6	1 2 3	
	3 4 5 6 7 8 9	7 8 9 10 11 12 13	7 8 9 10 11 12 13	4 5 6 7 8 9 10	
	10 11 12 13 14 15 16	14 15 16 17 18 19 20	14 15 16 17 18 19 20	11 12 13 14 15 16 17	
	17 18 19 20 21 22 23	21 22 23 24 25 26 27	21 22 23 24 25 26 27	18 19 20 21 22 23 24	
	24 25 26 27 28 29 30	28	28 29 30 31	25 26 27 28 29 30	
Foundation	May	June	July	August	Stairs (I)
1	Mo Tu We Th Fr Sa Sa	Mo Tu We Th Fr Sa Su	Mo Tu We Th Fr Sa Su	Mo Tu We Th Fr Sa Su	(1)
	30 31	1 2 3 4 5	1 2 3	1 2 3 4 5 6 7	
	2 3 4 5 6 7 8	6 7 8 9 10 11 12	4 5 6 7 8 9 10	8 9 10 11 12 13 14	
	9 10 11 12 13 14 15	13 14 15 16 17 18 19	11 12 13 14 15 16 17	15 16 17 18 19 20 21	
	16 17 18 19 20 21 22	20 21 22 23 24 25 26	18 19 20 21 22 23 24	22 23 24 25 26 27 28	
	23 24 25 26 27 28 29	<b>27 28 29 30</b>	25 26 27 28 29 30 31	29 30 31	Superstructure
	September	October	November	December	Ouperstructure
	Mo Tu We Th Fr Sa Su				
	1 2 3 4	31 1 2	1 2 3 4 5 6	1 2 3 4	
	5 6 7 8 9 10 11	3 4 5 6 7 8 9	7 8 9 10 11 12 13	5 6 7 8 9 10 11	
	12 13 14 15 16 17 18		14 15 16 17 18 19 20	12 13 14 15 16 17 18	
	19 20 21 22 23 24 25	17 18 1 20 21 22 23	21 22 23 24 25 26 27	19 20 21 22 23 24 25	
	26 27 28 29 30	24 25 26 27 28 29 39	28 29 30	26 27 28 29 30 31	
L					I
Sta	airs (II)				
		Elevator/St	airwell Walls	Installation of	
	White Noise Te	est		Balloon Framing	

## Construction (Nonstructural)



Internal Partition walls (ONGOING)

Electrical system (ONGOING)

Fire sprinklers (ONGOING)

**HVAC** 

Gas Pipes

Elevator

Waterproofing paint on balloon framing

Precast concrete cladding




Cooling Tower





Isolators arrived on site

## **Construction (Nonstructural)**



## Research Activities (pre-test)

- During construction, research team needed to multi-task
  - Conduct pre-test simulations (guide motion selection, instrumentation layout)
  - Watch, document, & take part in (as feasible) construction
  - Create instrumentation drawings
  - Watch, document, & take part in (as feasible) construction
    - ✓ We created a weekly construction log documenting all key construction activities digitally & disseminating them during a weekly team meeting



# Instrumentation, Test Planning & Sequencing SPECIFICS

#### Instrumentation

#### **VIDEO CAMERAS**

Provided by industry partners and by NEES@UCSD



#### **ANALOG SENSORS**

Three DAQs provided by NEES@UCSD and NEES@UCLA (UCLA1 and UCLA2)





#### **GPS**

Provided by the Scripps Institute of Oceanography



#### STILL CAMERAS

High resolution digital

We produced an entire 200pg report summarizing the instrumentation (cameras & analog sensor details)


#### **Analog:**

420 channels: NEES@UCSD + 90 channels: NEES@UCLA

= 510 channels


<u>Structure (~1/3) + NCSs (~2/3)</u>

#### **Analog Sensors**



#### Every sensor was:

- -Physically attached to the structure
- -Provided a unique name
- -Cable-based connected to the DAQ
- -Connected to a NODE
- -Visually & digitally documented (during testing as well!)





Medical freezer: Level 5

## **Video Imagery**

#### > The importance of high quality video cannot be understated

Table 1. Cameras used during seismic test phase.

Table 1. Cameras used during seismic test phase.							
Camera Type	Typical Image of Camera	Number of Cameras	Uncut Data Collected (GB)	Sample Snapshot of Camera View			
IP	lens .	56	~140		TEST BUILDING  IP Cameras	CONTROL ROOM DVR Server	
Coax		16	~43		SMC EZ Switch	IP Address  Cisco 3750 Switch	Cat 6 cable Wireless
HD Camcorder	HONY LINE AND A MARKET	8	~215			SERVER ROOM	
GoPro HD HERO2		7	~200	3N			

<sup>\*</sup>Note: Not all cameras were used for each earthquake motion.

## **Panoramic Imagery**



Third Floor (before fire testing)

Third Floor (after fire testing)



## Phase 1: <u>Base isolated</u> building-nonstructural system



4 days of seismic motion testing (April 16-27, 2012)

- 1. High damping rubber, cylindrical bearings placed @ each corner of building (4 total)
- 2. Building elevated from shake table




#### **Building Lift**




- We lifted our ~700 ton building twice (to install & remove isolators)
  - Building was cast with a 12" pedestal, isolator was 3-1/16" taller, therefore we lifted it 4"
- Safety was of upmost importance; UCSD Site staff were outstanding in supporting and executing this effort
- > Process:
  - Propose a sequence of lift in close consultation site staff
  - Collect materials
    - ✓ Purchase/rent/pickup jacks (we used 8x enerpac pancake jacks, 200 & 240ton@10ksi; we rented 4 of these, site had 4)
    - ✓ Test jacks
  - Un-PT and unbolt vertical rods, unbolt pedestals
  - Install jacks
  - Install linear potentiometers & redundant needle valves
  - Maneuver plates
  - Install isolators (or pedestal for the second lift)


#### **Building Lift (artistic rendering, Gunthardt)**



# Phase 2: <u>Fixed-base</u> building-nonstructural system





### **White Noise Motions**




We performed WN before and after seismic tests to asses the state of the structure (SI)


# **Tracking the Table Performance**






# **Maximum Acceleration**






# Table Performance: Guidance for Subsequent Motions



# Motion selection, sequencing & scaling strategy

- Overlap between portion of BI & FB motions
- > < 0.5% Peak Interstory drift ratio (IDR) BI Phase
  - Service level hazards (~43yr event)
  - Preserve structure for FB phase
- Motions with varied characteristics
  - Motion from CA/West coast US
  - Long duration of shaking
- Achieve design performance objectives in building (FB)
  - 2-2.5% Peak IDR
  - 0.8g or so PFA
  - ~Design earthquake event
- Achieve well above design demands

### **Seismic Motions: Achieved**



# Phase 3: Controlled live fire, pressurization & smoke tests







days of live fire testing (May 23-25, 2012)

Test Execution, some informal guidance

# **SPECIFICS**

### Plan well in advance "between-motion activities"

- Safety inspection site staff NO ENTRANCE into test specimen
- Tier 1 video & data analysis
  - Rapid review of individual data channels
  - Safety & subsystem integrity checks
- Tier 2 video & data analysis
  - Specific components, subsystems
- > Tier 3 video & data analysis
  - More detailed analysis (as time allowed)
- Physical inspection research team
  - 2-3 research (core team) members were teamed with ALL invited industry partners (no industry partners were allowed to freely roam the building

### Continued....

- Functionality checks
- Compartment pressurization tests (WPI)
- Replenish water cooling tower
- Replace push-pull rods at PCC connections
- Replace damaged ceiling tiles
- Replace sensors, reposition cameras
- Reposition equipment, replace component of a subsystem as needed
- QuakeHold free BI; strapped FB
- **>** ...

# **Media Exposure**

- Large-scale tests are a terrific opportunity to provide visibility to our efforts as a research community
  - Video documenting the entire process (construction, testing, demolition)
- Look for help/suggestions/media teams to provide support and help document all aspects
- We held three key "media days"
  - UCSD-JSOE advertised (sent out media advisories & coordinated all incoming media groups)
  - All major national news channels were allowed on-site, several international media channels; interviewed project Pls & industry sponsors
  - Within one of these hosted an NSF-Live Science Webcast with Dr. Joy Pauschke (answering questions live between tests)




Media Exposure = Society Awareness




(there are many)

# A FEW IMPORTANT FINDINGS

# Phase 1: Base isolated building-NCS system




# Phase 2: Fixed base building-NCS system



Peak Res Failure of Stair Flight-**Landing Connections** 





BI1-CNP100 BI2-LAC100 BI4-SP100 BI5-ICA50 BI6-ICA100 **BI7-ICA140** FB1-CNP100 FB2-LAC100 FB3-ICA50 FB4-ICA100 FB5-DEN67


FB6-DEN100



Balloon framing clip detachment




# **Egress: Stairs**




# R

# Upper Flight–Slab Connection Plate Fracture






# **Drift-Compatible Façade Connections**




Damage Level:

Green=None Yellow=Minor Orange=Moderate Red=Severe

- 1) Intended performance of flexing connections
- 2) Unexpected yielding of sliding connections at low drift amplitudes




Flexing Connection



**Sliding Connection** 


# Colliding Corner – Ductile Fuse (new idea)






New corner system design to allow for smaller corner joints:


- <u>Elastic Drifts</u> → Gap closure
- <u>Inelastic drifts</u> → Impact but overload prevented by ductile fuse



# **Ductile, Colliding Corners**








<u>Connection Displacement</u> <u>(relative)</u>

## **Live Fire Tests**



Date	Sequenc e		
May 23, 2012	1. LBR-1		
	2. SBR		
May 24,	3. LBR-2		
2012	4. ES		
May 25,	5. EL-1		
2012	6. EL-2		

- Series of 6 fires, heat release rate (HRR) varying from about 0.5 MW to about 1.5+ MW
- Goals: (a) obtain temperature data for simulations, (b) assess smoke spread, (c) assess potential for flame spread, and (d) assess potential for structural impact
- Burn time limited to about 15 minutes
- Heptane fuel burned in pans (1 to 3, depending on desired fire size)

# **EL Fire Test 1/2: Representative Effects**



**Elevator controls melted** 



**Spalling of concrete slab** 



Intumescing of fire stop

With the damage to the gypsum wall system due to seismic motions, the fire was able to bring the system to failure much more quickly than any fire rating would suggest



Failure of wall system (after EL 2 test)

# **Egress: Elevator**




Door Jamb After FB5-DEN67 (functional)



Door Jamb After FB6-DEN100 (non-functional)






# **Elevator Improvements**





Schindler Corp

# Phase 2: Fixed base building-NCS System



(there are many)

# **PROJECT ACCOLADES**

# Project Accolades: Human Resources



UCSD: Astroza, Ebrahimian, Wang (PhD 2015) & Pantoli, Chen (PhD 2016)

- WPI: Park (2014 PhD); Kim (MS 2013)
- > SDSU: Espino & Aranda (MS 2012, 2014)
- Univ of Bologna: Selva & Bezzi (MS 2012, 2014)
- > NEES-REU (8 UGs from SJSU, VPI, UCSD)
- > NEES-RET: 6 SD teachers outfitted with mini-shake tables

> 3 Payload projects: WPI (fire), SIO (GPS) & Cal Poly SLO (mini-

shakers)









# **Project Accolades: Technical Contributions**

- Award in Excellence for Research Projects (Western States Seismic Policy Council, 2014)
- > 5-part Technical Report Series (UCSD), 2-part Technical Report Series (WPI)
- Numerous technical papers (conference, journal)
  - 2-part Earthquake Spectra (overarching, 2015)
  - "Data Paper" Earthquake Spectra
  - System ID: Astroza et al., Modeling: Ebrahaminian, Wang, Facades Pantoli et al., Egress Systems: Wang
- Large volume of data (image, analog) publically available -> NEESHub
- ASCE 7-16 Code Changes
  - Precast cladding connections
  - Stair (drift limits, importance factor)
  - Elevator detailing

# **Project Accolades: Public Impact**

Professional video publication (UCSD-TV)







- Educational video module series (4-part structural; 2-part nonstructural; geared towards undergraduate learning)
- Documented extensive media exposure

# Demolition – Don't forget it!


> \$135k ++ lots of help from industry (\$98k in just structural concrete; removal of ceiling, stairs, elevator by others)





# The real stars of the show....







Base	Station-scale (Earthquake)	Name	Type	Notes	
	Canoga Park-100%	BI-1: CNP100	SM	Serviceability level	
	(1994 Northridge earthquake)				
	LA City Terrace-100%	BI-2:LAC100	SM	Serviceability level	
	(1994 Northridge earthquake)				
	LA City Terrace-100%	BI-3:LAC100	SM	Serviceability level	
T 1 4 1	(1994 Northridge earthquake)	DI 4 CD100		T 1 4'	
Isolated	San Pedro-100%	BI-4:SP100	AM	Long duration	
(BI)	(2010 Maule-Chile earthquake)	DI 5.ICA50	ANT	I and drugtion	
	ICA-50% (2007 Disage Porty conthaughts)	BI-5:ICA50 AM		Long duration,	
	(2007 Pisco-Peru earthquake) ICA-100%	BI-6:ICA100	AM	multiple runs Long duration,	
	(2007 Pisco-Peru earthquake)	DI-0.1C/1100	AIVI	multiple runs	
	ICA-140%	BI-7:ICA140	AM	Long duration,	
	(2007 Pisco-Peru earthquake)	<b>D1</b> 7.10/11 10	7 1111	multiple runs	
0.6	1	2		1	
0.0		7 2		BI1:C	NP100
					AC100
45		1.5	<u> </u>	I	P100
			<b>\</b>	BI5:10	
		<u> </u>		BI6:I0	CA100
).3				—— BI7:10	CA140
		(g) 8 1	W		
	MACH		<b>//W//</b>	Mal .	
15		0.5			
		7	MAN CO	bally	
0	1 2			1 2	
-	<del>-</del>	•		<del></del>	

Base	Station-scale (Earthquake)	Name	Type	Notes
	Canoga Park-100%	FB-1:CNP100	SM	Low amplitude -
	(1994 Northridge earthquake)			expect service
	LA City Terrace-100%	FB-2:LAC100	SM	Low amplitude -
	(1994 Northridge earthquake)			expect service
	ICA-50%	FB-3:ICA50	AM	Long duration,
Fixed	(2007 Pisco-Peru earthquake)			multiple runs
(FB)	ICA-100%	FB-4:ICA100	AM	Long duration,
	(2007 Pisco-Peru earthquake)			multiple runs
	Pump Station #9-67%	FB-5:DEN67	SM	~Target design
	(2002 Denali eq.)			demand
	Pump Station #9-100%	FB-6:DEN100	SM	~>50% larger than
	(2002 Denali eq.)			Design demands

